

Bellevue's Traffic Adaptive Signals



ITE Quad Mtg
April 18, 2011



What we'll cover

- SCATS Phase 1 Implementation
- SCATS Operations
 - Responsiveness
 - New Features
 - Some Initial Results
- 2011 Program and Beyond
- Final Thoughts



Background

- New Signal System funded – 2008
- Comm. system upgraded – 2008 to 2011
- Signal System Study – 2009
- SCATS Traffic Adaptive – May 2010



Downtown Bellevue 2008



Bellevue ATMS



Bellevue Fiber Trunks


SCATS Implementation

- Initial SCATS deployment – **Phase 1**
 - Downtown
 - Factoria



SCATS Phase 1

- SCATS Traffic Adaptive – 31 Intersections
- Downtown and Factoria
- Target Completion – end of 2010



• NE 8th Street - 100th to 112th
• Bellevue Way - Main to 12th
• NE 4th Street - Bellevue Way
to I-405 NB on/off ramp



• Factoria Blvd - Newport Way to SE 32nd St

SCATS Phase 1

- Council Award July 2010
- Software/Hardware Testing Summer/Fall 2010
- Installation October 2010
- Traffic Adaptive Active Early November
- System Adjustments and Training – November & December

TRANSCORE



SCATS Phase 1

Summary – Phase 1


- 31 intersections completed on time and within budget
- Successful Effort
 - City staff (engineers/signal shop)
 - TransCore ITS
- Only City in Washington State



Operations

Objectives:

- Reduce delay
 - Vehicles
 - Pedestrians
- Adapt quickly to changing traffic conditions
- Gain New Features



Signal System

Why “Traffic Adaptive”?

Signal Coordination Methods:

- Time of Day Coordination
- Traffic Responsive Coordination
- Traffic Adaptive



Why Traffic Adaptive?



Signal Coordination

- Group of signals work together to achieve an objective
- All signals in group typically have same cycle length

Why Traffic Adaptive?




Time of Day Coordination

- Staff counts intersections on a “typical” day
- Engineer designs coordination plans (AM, Noon, PM, Off Peak, Etc)
- Plans implemented by time of day
- Plans don’t respond to changes in traffic



Why Traffic Adaptive?




Loop Detector

Traffic Responsive Coordination


- Detector continuously sends traffic data to the traffic computer
- Traffic computer selects plan based V+K0, not time of day
- Better method than time of day
- Traffic only monitored at 1 location; only 2-5 plans to select from

Why Traffic Adaptive?



- Traffic Adaptive

Why Traffic Adaptive?




- Traffic Adaptive
 - Continuously obtain traffic data from all lanes at all intersections


Why Traffic Adaptive?



- Traffic Adaptive
 - Data fed to central computer via communication system
 - Computer sends new coordination plan every cycle



Operations




SCATS Objectives

Select cycle length, splits and offsets to achieve

- Minimum stops with light demand
- Minimum delay with normal demand
- Maximum throughput with heavy demand


Operations – SCATS Downtown



Operations – Responsiveness



November 23rd, 2010 Snow Day (Tuesday)



Operations – Responsiveness



© Bellevue Nov 30, 2010 12:52 PM


Truck Accident Closes NE 8th St

Operations – New Features

- Flashing Yellow Arrow (FYA)
 - By Time of Day or Adaptive Trigger



Flashing Yellow Arrow - Drivers may proceed with left turn after yielding to oncoming traffic and pedestrians



Factoria Blvd & Newport Way FYA

Operations – New Features


EXAMPLE

- Factoria Blvd & Newport Way – South to East Left Turn
Old System – Protected Left Only
SCATS – FYA by Time of Day



Operations – New Features

- Factoria Blvd & Newport Way – RESULTS
 - Delay Reduction Sample – Weekday PM peak
 - Old Delay = 38 sec/veh
 - SCATS Delay = 16 sec/veh
 - 58% Reduction



Operations – New Features

- Phase Reservice
 - NE 4th St at NB I-405 on-ramp
 - Factoria Blvd at WB I-90 on-ramp




Eastbound NE 4th Queue to NB I-405
(March 1 & 2, 2011)

EB 4th Queued Past 110th:

	Start	End
Old System	4:10pm	7:00pm
SCATS	4:40pm	6:30pm

Result = 1 hr less congestion



Operations – New Features

- Phase Reservice
- Ped Reservice
- Ped Advance
- Transit Signal Priority



Operations – Results

- Flashing Yellow Arrow - Results

Intersection	Annual Delay Reduction (hours)	Annual Public Benefit (\$)
Factoria Blvd & Newport	7000 hrs	\$70,000
NE 8 th St & 100 th	8100 hrs	\$81,000
Richards Rd & SE 32 nd	2700 hrs	\$27,000
Bellevue Way & NE 12 th	6400 hrs	\$64,000
5 Others	2000 hrs	\$20,000
TOTAL	26,000 hrs	\$260,000

Operations – Results


Intersection Delay Change Sample
(Delay Reduction due to SCATS)
January 25, 2011

Intersection	8am-9	10am-11	Noon-1pm	3pm-4	5:30-6:30
BelWay/8th					
Factoria /SE 38 th					
NE 4 th /112th					
BelWay/12th					
KEY:					
Little or no change					
Delay reduction > 10%					
Delay reduction > 20%					

Overall Delay Reduction approx. 10%

Operations – Results

Factoria Blvd
Travel Time – SCATS vs Old System
(PM Peak)
Feb 15 & 16, 2011



Operations – Results

NE 8th Street & NE 4th Street
Travel Time – SCATS vs Old System
(2 pm to 6 pm)
February 15 & 16, 2011

- NE 8th Street – Bellevue Way to 112th Ave NE
 - Eastbound – 9 sec reduction
 - Westbound – 100 sec reduction
- NE 4th Street – Bellevue Way to I-405 NB ramp
 - Eastbound – 70 sec reduction
 - Westbound – 27 sec increase



Operations – Results

NE 8th Street & Bellevue Way
Pedestrian Crossing Opportunities
(7am to 8pm)

8% Increase




2011 and Beyond



2011 and Beyond


Current Status

- Old System (Computran)
 - 52 intersections, 28%
- Bridge System (i2TMS)
 - 93 intersections, 51%
- Traffic Adaptive (SCATS)
 - 38 intersections, 21%



Project Phasing

- Phase 1 – complete
- Additional 5 phases needed
- 1 Phase per year
- 30 signals per phase
- Completion 2015




SCATS Phase 2 - 2011

2011-2012 and Beyond

SCATS Phase 2

- 2011
- Finish Downtown Corridors
- 37% Completion



2011-2012 and Beyond

SCATS Phase 3

- 2012
- 148th Avenue NE/SE
- 53% Completion



2011-2012 and Beyond

SCATS Phase 4

- 2013
- 69% Completion



SCATS Phase 5

- 2014
- 88% Completion



SCATS Phase 6

- 2015
- Completes Project



Project Cost

Description	Cost
■ Comm System, Studies, Equipment, Labor - 2008 to 2011	\$2,000,000
Phase 1 - 2010	\$630,000
Phase 2 - 2011	\$480,000
Phase 3 - 2012	\$475,000
Phase 4 - 2013	\$475,000
Phase 5 - 2014	\$475,000
Phase 6 - 2015	\$450,000
TOTAL	\$4,985,000

Final Thoughts

Spot vs Systematic Investments



NE 8th St Widening
600' long lane addition
\$4,000,000 cost
\$170,000/yr benefit




SCATS Phase 1
4 key corridors, 31 intersections
\$630,000 cost
\$1,500,000/yr benefit

Final Thoughts

- Traffic Adaptive will grow quickly



SCATS Demo/TMC Tour



Bellevue's Traffic Adaptive Signals



mpoch@bellevuewa.gov




QUESTIONS?




Review

- Current Signal System Obsolete
- PW-R-155 begins 2009
- Communication system upgraded
- Signal System Study
- SCATS Traffic Adaptive – May 2010
- SCATS Phase 1 Contract – July 2010




Operations

- Bellevue Way and NE 8th St
 - Mid-Morning, Mid-Week Delay Sample (10:00 hour)
 - Old Delay = 38 sec/veh
 - SCATS Delay = 29 sec/veh
 - 24% Reduction
 - Approximately \$XX,XXX/yr in travel time savings



Operations




- Traffic Adaptive
 - Continuously obtain traffic data from all lanes at all intersections

Operations



- Traffic Adaptive
 - Data fed to central computer via communication system
 - Computer sends new coordination plan every cycle

Volume and Cycle Length Comparison





Operations


Computran Coordination (old signal system)




Operations – SCATS Downtown




Operations – SCATS Downtown



Operations - Responsiveness




Operations - Responsiveness



Operations - FYA

- Factoria Blvd & Newport Way – RESULTS
 - Delay Reduction Sample – Weekday PM peak
 - Old Delay = 38 sec/veh
 - SCATS Delay = 16 sec/veh
 - 58% Reduction
 - Approximately \$60,000/yr in travel time savings



Operations – Results

Intersection Delay Modeling Results
(Delay Change due to SCATS)

Intersection	8am-9	10am-11	Noon-1pm	3pm-4	5:30-6:30
BelWay/8th	-20%	-12%	+3%	0%	+4%
Factoria /SE 38 th	+2%	-3%			-51%
NE 4 th /112th	-6%	-9%	-13%	-13%	-10%
BelWay/12th	-23%	-23%	-19%	-24%	-13%

Operations – Results

Intersection Delay Modeling Results
(Delay Change due to SCATS)

Intersection	8am-9	10am-11	Noon-1pm	3pm-4	5:30-6:30
BelWay/8th	>20%	>10%			
Factoria /SE 38 th					>30%
NE 4 th /112th			>10%	>10%	>10%
BelWay/12th	>20%	>20%	>10%		>10%

2011-2012 and Beyond

Funding Picture


- PW-R-155 (Traffic Computer System Upgrade)
 - 2011 = \$435,000
 - 2012 = \$390,000
- Federal TSCP Grant
 - \$360,000
 - Council Acceptance Sept. 2010



2011-2012 and Beyond

SCATS Phase 4

- 156th Crossroads
- Bel-Red Rd
- NE 20th/Northrup
- NE 8th St East Bellevue
- 29 Intersections
- Cost Estimate = \$348,000
- Funded PW-R-155
- Implementation 2013
- 69% Completion



2011-2012 and Beyond

SCATS Phase 5

- Bellevue Way south/north
- SE 8th St @ I-405
- 140th Ave SE
- Lakemont
- 29 Intersections
- Cost Estimate = \$348,000
- Request Funding '13-'14 Budget
- Implementation 2014
- 88% Completion



2011-2012 and Beyond

SCATS Phase 6

- Completes SCATS Project
- Isolated Intersections
- 23 Intersections
- Cost Estimate = \$276,000
- Request Funding '13-'14 Budget
- Implementation 2015

